BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/07/2016-17 Dated: 27-02-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 11

Name of Work:- Providing asphalting to main and cross roads of Amba Bhavani layout in Attur ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri TULASIRAM REDDY	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no141,PWD SR 2016-17)	Cum	934.50	83.80	Rupees eighty three and paise eighty only
2	Removing B.S slab of drain and stacking (P.No 25 I.No 5.32)	sqm	1215.00	63.00	Rupees sixty three only
3	Refixing stone slabs of drains and pointing in CM(1:3)(P.No 25 I.No 5.33)	Sqm	1215.00	78.00	Rupees seventy eight only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete **do 7.5 cms** thick(P.No 25 I.No 5.31.1)	sqm	405.00	655.00	Rupees six hundred fifty fivet only
5	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications (Item no17.1,Page no133,PWD SR 2016-17	Cum	934.50	70.00	Rupees seventy only

	Description	Unit	Approved Qty	Approved Rates Sri TULASIRAM REDDY	
				Rate	Rate in Words
6	KSRRBM400-17,Providing, laying, spreading andcompacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site,laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired dencity complete as per specifications.MORTH Specification No.406(Item no20.18,Page no157 ,PWD SR 2016-17)	Cum	547.50	1741.00	Rupees one thousand seven hundred forty one only
7	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH Specifications No502 (ITEMNO21.6,Page no157,PWD SR 2016-17)	sqm	2850.00	27.00	Rupees twenty seven only
8	KSRRB M500-19: Providing and laying bituminous concrete 40mm thick with 100/120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH specification NO. 509, No.165 Item No. 21.22.2.PWD SR 2016-17	Cum	114.00	7379.00	Rupees seven thousand three hundred seventy nine only

ವೆ ಲಕ್ಷ್ಮಿರೆಡ್ಡಿ

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.